ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Notification dated 7th November 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 29th November 1935 (2 P.M.), for the construction of a compound wall on western and northern sides of the Laboratory Block attached to Malleswaram High School at Bangalore (Subedar Chattram Road). An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 (one hundred and fifty only) in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for construction of a compound wall on western and northern sides of the Laboratory Block attached to Malleswaram High School at Bangalore (Subedar Chattram Road) "in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted. Transfer of works to third parties by selected contractors will not be countenanced by the Department and in the case of any such attempt, the earnest money is liable to be forfeited at the discretion of the Superintending Engineer.

Abstract estimate of quantities for constructing compound wall.

No.	Items of work	Per	Estimate rate.	Quantity	Tendered rate.
			Rs. a. p.		
1	Earthwork excavation foundation	C.yd.	0 3 6	91	
2	Filling in foundation and basement with stone in clay	C.ft.	0 3 6	3,915	
3	Burnt brick in clay	,,	0 3 6	2,931	
4	Mortar plastering	Sqr.	3 0 0	69·24	
5	Mouldings 3" cornice to pillars	R.ft.	0 4 0	1,339	
6	Moulding detail coping with brick work, etc., complete	R.ft.	0 8 0	1,006	
7	Moulding pillars heads complete	Each	0 12 0	74	
8	Earthwork excavation for levelling and forming grounds	C.yd.	..	..	

Notification dated 11th November 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 4th December 1935 (2 P.M.) for constructing Subsidiary Buildings for the New Mental Hospital at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one thousand two hundred only (Rs. 1,200) in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for

constructing Subsidiary Buildings for the New Mental Hospital at Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Transfer of works to third parties by selected contractors will not be countenanced by the Department and in the case of any such attempt the earnest money is liable to be forfeited at the discretion of the Superintending Engineer.

Abstract estimate of quantities of Subsidiary Buildings in the New Mental Hospital at Bangalore.

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation for foundation and filling in basement	C.yd.	0 3 6	293	
2	Laying stone jelly concrete in lime mortar 1 : 2 : 4 for foundation	C.ft.	0 3 6	2,250	
3	Size stone in clay for foundation and basement with through bond slabs 6′ apart	,,	0 4 0	7,071	
4	Burnt stone slabs 6″ thick one line dressed including hoistings and fixings	S.ft.	0 6 0	2,512	
5	Do do 2 lines dressed ..	,,	0 8 0	214	
6	Burnt brick in clay	C.ft.	0 4 0	10,744	
7	Teakwood doors with frames 4″×5″ shutters 1½″ thick fully panelled including brass fittings..	S.ft.	1 8 0	611	
8	Do do 3½″×5″ frames 1½″ panel shutters with steel fittings	,,	1 6 0	141	
9	Teakwood battened doors 1¼″ thick shutters frames 3½″×4½″ including steel fittings	,,	1 4 0	68	
10	Teakwood glazed windows and ventilators sashes 1¼″ thick, frames 3½″×5″ by ¾″ iron bars, fittings etc., complete	,,	1 12 0	791	
11	Teakwood panelled shutters for almirahs ..	,,	1 0 0	30	
12	Pillars with wire cut quadrant bricks in cement mortar 11″ dia. at bottom 10″ at top 10 ft. high with 2 cir. bond slabs ornamental base and capital, plastering etc., complete as per drawings	No.	20 0 0	13	
13	9″ square stone pillars 9′ high with ornamental base and capital as per drawing, surface two lines dressed	,,	30 0 0	9	
14	Circular pillars at per item No. 12, 9″ dia. at bottom and 8″ at top, 6¾′ high	,,	..	5	
15	Wire cut bricks in lime mortar 1 : 2 with expanded metal suits in cement mortar at every 5th course for partition walls	C.ft.	0 10 0	513	
16	Rolled steel girders and joists including hoisting and fixing with one coat of red oxdie paint ..	cwt.	10 8 0	44	
17	Boxing double girders with slab and brick in mortar wirings plastering etc., complete	R.ft.	0 8 0	315	

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		Rs.
18	R. B. C. Flat terrace to take a superimposed load of 1½ cwt. per square 3″ surki concrete with necessary slopes at top, ½″ cement plastered bottom etc., complete	Sqr.	70 0 0	28.01	
19	Teakwood wrought and put up with two coats of wood oilings	C.ft.	5 4 0	184.00	
20	Teakwood king post truss to carry Mangalore Tile roofings 14′ clear span wise 3⅓′ including hoisting and fixing	No.	25 0 0	2	
21	Mangalore Tile roofing 1st Class with 2″×1″ reepers as per specification	Sqr.	25 0 0	37.89	
22	Do do ridges with pointings ..	R.ft.	0 12 0	298	
23	Chunnam plasterings over brick wall	Sqr.	3 4 0	211.93	
24	Mortar bands of the valley portion of roofing to throw off rain water with 1″ thick planks underneath	R.ft.	1 0 0	70	
25	9″ cornice as per drawing	R.ft.	0 12 0	492	
26	Parapet wall with brick in mortar 9″ thick base and top cornice as per drawing etc., complete 2½′ high	,,	1 8 0	21	
27	Do do do 1½′ high ..	,	1 4 0	258	
28	9″ coping with brick in mortar over compound wall as per drawing complete	,,	0 8 0	128	
29	White washing, 2 coats	Sqr.	0 4 0	194.00	
30	Colour do	,,	0 6 0	73.00	
31	Flooring with 1½″ cement concrete 1 : 2 : 4 over 3″ lime concrete 1 : 2 : 4, ½″ cement plaster at top with red ochere finish joints etc., complete	,,	25 0 0	42.14	
32	Silicate painting to doors and windows 2 coats..	,,	3 4 0	32.56	
33	Cement pointing to basement with cut lines ..	,,	3 0 0	12.10	
34	Mortar " patti " alround door	R.ft.	0 2 0	28	
35	Providing and fixing 6″ eave boards	,,	0 8 0	289	
36	Providing and fixing down water pipes 3½″ to 4″ dia. with zinc sheet	,,	0 7 0	100	
37	Parapet wall as per item No. 26, 2′ high ..	,,	1 6 0	213	
38	Arch work with brick in mortar	C.ft.	0 6 0	15	

Notification dated 11th November 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer Buildings Division, up to 4th December 1935 (2 P.M.) for Constructing the new Mental Hospital at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a depoist of Rupees Five thousand only (Rs. 5,000) in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for Constructing Administrative Block in the New Mental Hospital at Bangalore " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Transfer of works to third parties by selected contractors will not be countenanced by the Department, and in the case of any such attempt the earnest money is liable to be forfeited at the discretion of the Chief Engineer.

Abstract estimate for the proposed New Mental Hospital Buildings, Bangalore [Main Buildings of Hospital. 1. Administrative Block including Tower. 2. Corridors. 3. General Wards, one for Male and [illegible] for Female].

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation, filling in basement watering, tamping etc., complete ..	C.yds.	0 3 6	1,638	
2	Laying burnt stone jelly concrete for foundation in lime mortar (1 : 2 : 4)	C.ft.	0 3 6	18,930	
3	Size stone in lime mortar (1 : 2) for foundation and basement with through bond slabs 6′ apart ..	,,	0 5 0	28,058	
4	Size stone in mortar for superstructure ..	,,	0 5 0	1,609	
5	Burnt brick in clay for superstructure	,,	0 4 0	49,110	
6	Burnt stone slabs 6″ thick, one line dressed, including hoisting and fixing for basement slabs below walls, sills and lintels of doors etc. ..	S.ft.	0 6 0	11,540	
7	Burnt stone slabs 6″ thick exposed surface 2 line dressed including fixing etc., for verandah basement and steps	,,	0 8 0	2,208	
8	Wirecut bricks in lime mortar for partition walls, 9″ thick	C.ft.	0 10 0	1,110	
9	Wirecut brick in lime mortar for partition walls 4½″ thick with cement mortar and expanded metal strips reinforcement at every 5th course ..	,,	0 10 0	994	
10	T. W. doors with 4″×5″ teak wood frames, shutters 1½″ thick ⅓ panelled and ⅔ glazed, including brass fittings and fixing etc., complete. ..	S.ft.	1 12 0	2,145	
11	Teakwood doors with 3½″×4½″ frames 1¼″ panelled shutters brass fittings etc., complete for lavatory and bath room doors	,,	1 8 0	636	
12	Teakwood windows with frames 3½″×5½″, shutters 1½″, glazed shutters inside, panelled outside ¾″ iron bars brass fittings, etc., complete ..	,,	2 8 0	3,439	
13	R. C. perforated ventilators	,,	1 0 0	380	
14	Rolled steel girders and joists including hoisting and fixing with red-oxide painting	cwts.	10 0 0	917	
15	Boxing girders with slabs and brick in mortar, wiring, plastering outside etc., complete ..	R.ft.	0 8 0	2,744	
16	Pillars of quadrant wirecut bricks in cement mortar 13″ dia. at bottom 11″ at top with 3′ circular bond slabs ornamental base and capital as per drawing plastering etc., complete with dressing at each pillar	No.	25 0 0	160	
17	Reinforced brick concrete flat terrace to carry a superimposed load of 1½″ cwts. per s.ft. 3″ surki concrete and 2 course of flat tiles and plastered with necessary slopes at top and smooth ceiling plastering at bottom span up to 10 feet ..	Sqr.	70 0 0	323.32	
18	Do do for Tower portion with ½″ cement plastering at top and bottom span up to 13 feet	,,	80 0 0	1.96	
19	Chunam plastering over stone masonry wall ..	,,	4 0 0	14.18	
20	Ornamental plastering over stone masonry wall as per drawing	,,	8 0 0	2.04	
21	Chunam plastering over brick wall	,,	3 4 0	742.57	
22	Plain cornice 6″ as per drawing	R.ft.	0 6 0	913	
23	Do 9″ do	,,	0 8 0	2,170	
24	Plain parapet wall 9″ thick with brick in mortar 1½′ high with weep holes base and top cornice as per drawing, plastering etc., complete ..	,,	1 8 0	2,170	
25	Do do 1′ high	,,	1 4 0	913	

No.	Items of work	Unit	Rate	Quantity	Rate to be quoted
			Rs. a. p.		Rs.
26	Ornamental parapet 9″ thick and 2′ high as per drawing	R.ft.	2 8 0	12	
27	Flooring with 1½″ cement concrete (1 : 2 : 4) over 3″ lime concrete (1 : 2 : 4), 1½″ cement plaster at top with red ochere finish joints etc., complete	Sqr.	25 0 0	246.27	
28	White washing 2 coats	,,	0 4 0	902	
29	Colour washing 2 coats	,,	0 6 0	165	
30	Silicate painting to doors and windows ..	,,	3 4 0	193.18	
31	Cement pointing to basement with cut lines ..	,,	3 4 0	30.78	
32	Quoin dressing for basement	R.ft.	0 1 0	60	
33	Providing and fixing R. C. balustrades with granite slabs base and coping as per drawing ..	,,	3 8 0	52	
34	Providing and fixing zinc down-water pipes 3½ to 4″ dia.	,,	0 7 0	350	
35	Extra work for curved construction in stone masonry	C.ft.	..	..	
36	Do dressing and wastage in curved portion	S.ft.	..	..	
37	Constructing brick masonry ornamental tower about 28 feet high above the height of building (Administrative block) 14 feet bottom square up to 4. 12 feet bottom square up to 20. 8 feet bottom square up to 4	C.ft.	1 0 0	3,868	
38	Do do in stone masonry ..	,,	1 0 0	3,868	

A. TANDONI RAO,
Executive Engineer.

LOWER CHANNELS DIVISION, MYSORE.

Notification dated 9th November 1935.

" It is hereby notified for the information of the public that the Offices of the Executive Engineer Lower Channels Division, Mysore, and of the Assistant Engineer, No. 1 Channels Sub-Division, Mysore, will be shifted from the present building to the Bungalow of Mr. Turuvekere Basavaraj Urs, situated in Kantharaj Urs Road, Mysore, from the 18th instant. All communications intended for the above offices may thereafter be sent to the new address ".

S. MUTHUSWAMY IYER,
Executive Engineer.

KRISHNARAJASAGARA DIVISION,

Abstract Notification dated 5th November 1935.

The public are hereby informed that if the amounts of deposits detailed in the Notification, dated 21st October 1935, published in the *Mysore Gazette*, dated 31st October 1935, (*vide* page 1988, are not claimed before 21st November 1935, they will be credited to Government.

N. KRISHNAIENGAR,
Executive Engineer.

HASSAN DIVISION.

Notification dated 11th November 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 4th December 1935 up to 3 P.M. for restoring Kudargundi Doddakere Major Tank, Register No. 505 of Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Kudargundi Doddakere Major Tank Register No. 505 of Hassan Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Shimoga Circle, Shimoga, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of the cost of restoring Kudargundi Doddakere, Register No. 505 of Hassan Taluk.

No.	Items of works	Quantity	Per	Rate	Cost
				Rs. a. p.	Rs.
1(*a*)	Earth to bund with watering and consolidation including all lead and lift	8,246	C.yd.	0 5 0	
(*b*)	Lead and conslidation charges to earth available from approach and draft clearance foundation excavation of weirs and excavation of bund between C. S. 1 and 2 up to R.L. 50.00 ..	1,366	C.yd.	0 2 0	
2	Turfing the slopes of bund	8,064	S.yd.	0 0 9	
3	Jungle clearing, removing grass and trees ..	39	gross	3 0 0	
4	Cutting grips and step on the slopes of old bund and using the excavated earth to bund with watering and tamping	37	grade	5 0 0	
5	Excavating, opening out and refilling with new earth with consolidation ant hills on old bund..	L. S. Rs.		..	40
6	Providing and fixing new grade stones	2	Each	2 0 0	
7	Providing and fixing new Index stones	38	,,	0 12 0	
8	Providing and fixing new date and Register No. stone	1	,,	4 0 0	
9	Providing and fixing new B. M. stone	1	,,	3 0 0	
10	Removing and refixing old B. M. stone after figuring and painting	1	,,	1 0 0	
11	Removing and resetting old grade stones with painting, figuring etc., complete	36	,,	0 4 0	
12	New stone revetment with jelly filling and jelly wedging etc., complete	1,392	C.yd.	1 10 0	
13	Removing and resetting old stone work to be required slope with necessary jelly filling etc., complete	L. S. Rs.		..	300
	Left Waste-Weir 250′ *long at* 50.00.				
1	Draft and approach clearing and using the earth got to bund with watering and consolidation ..	L. S. Rs.		..	60
2	Earth work excavation	756	C.yd.	0 3 0	
3	Stone jelly concrete in surki mortar	1,193	C.ft.	0 4 6	
4	Burnt brick in surki mortar	1,268	,,	0 5 0	
5	Plastering with surki mortar	14.42	Sqr.	4 8 0	
6	Cement concrete coping 1 : 2 : 4	199	C.ft.	1 0 0	
7	Rough stone apron with jelly filling and wedging etc., complete	150	C.yd.	1 10 0	

No.	Items of work	Quantity	Per	Rate	Cost
				Rs. a. p.	Rs.
	Right Waste-Weir 130′ *long at* 50.00.				
1	Draft and approach clearing and using the earth got to bund with consolidation	L. S. Rs.		..	
2	Earth work excavation	210	C.yd.	0 3 0	
3	Stone jelly surki concrete for foundation ..	978	C.ft.	0 4 6	
4	Burnt brick in surki mortar	1,772	,,	0 5 0	
5	Plastering with surki mortar	14.18	Sqr.	4 8 0	
6	Cement concrete coping 1: 2 :4	109	C.ft.	1 0 0	
7	Rough stone work, new, with jelly filling and wedging etc., complete	117	C.yd.	1 10 0	
8	Constructing apron with available stones and new jelly filling	58	,,	0 12 0	
9	Providing and fixing pin slabs for apron at 4′ intervals	299	S.ft.	0 4 0	
	Silt Dams.				
	Providing 2 silt dams against feeder halla to arrest silt	L. S. Rs.		..	250
	Sluice No. I at R.L. 40.00.				
1	Earth work cut opening the bund and refilling the same with consolidation	276	C.yd.	0 6 0	
2	Excavating foundation for cistern and pipe ..	17	,,	0 3 0	
3	Stone jelly concrete in surki mortar	187	C.ft.	0 4 6	
4	Burnt brick in surki mortar	831	,,	0 5 0	
5	Plastering with surki mortar	5·53	Sqr.	4 8 0	
6	Providing and fixing 6″ thick burnt stone slabs in surki mortar	193	S.ft.	0 10 0	
7	Boring holes in orifice slabs	4	Each	1 0 0	
8	Providing and laying cast iron pipe 9″ diameter including carting jointing with hemp cement etc., complete. (Pipes will be supplied Departmentally)	60	R.ft.	4 0 0	
9	Providing and fixing Teakwood plug and rod with locking arrangements etc., complete	1	Each	10 0 0	
	Repairing Sluice No. 2 on the right side.	L. S. Rs.		..	250
10	Providing one recess in the middle of bund ..	do		..	80

Notification dated 11*th November* 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 3 P.M. on 2nd December 1935, for constructing Station and Office Building of Electrical Department at Hassan and Hole-Narsipur Towns (separately). An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred only in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for constructing Station and Office Building of Electrical Department at Hassan and Hole-Narsipur" in default of which tender will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Sl. No.	Items of work	Unit	Rate	Quantity
			Rs.	
	Earthwork excavation for foundation and filling in basement	C.yd.	0 3 0	74
2	Stone Jelly concrete in lime mortar	C.ft.	0 4 0	607
3	Size stone in lime mortar	,,	0 5 0	1,201
4	Burnt brick in lime mortar	,,	0 5 0	2,173
5	Burnt stone slabs 4″ to 6″ thick dressed and fixed in mortar	Sq.ft.	0 8 0	437
6	Providing and fixing teak-wood doors $1\frac{1}{4}$″ thick shutters $\frac{1}{2}$ glazed and $\frac{1}{2}$ pannelled with fittings, etc., complete	Sq.ft.	2 0 0	126
7	Providing and fixing teak-wood windows with glazed shutters inside and pannelled shutters outside with iron bars, etc., complete	Sq.ft.	2 8 0	122.5
8	Providing and fixing glazed ventilators	,,	1 8 0	54
9	Reinforced concrete jelly work as per drawing	,,	2 0 0	107
10	Providing and fixing Rolled Steel joists Tata's tested 10″ × 5″ and 5″ × $2\frac{1}{2}$″ with anticorrosive painting	Cwt.	12 0 0	23.5
11	Reinforced brick terrace with plastering below and concrete above complete	Sq.	65 0 0	11.01
12	Lime plastering	,,	4 0 0	43.68
13	Chocolate painting	,,	3 8 0	6.06
14	Cement concrete flooring 3″ thick with thick plastering above 1 : 2 : 4 Proportion	,,	20 0 0	10.35
15	Plain 3″ cornice as per drawing	R.ft.	0 10 0	190
16	Plain parapet wall $1\frac{1}{4}$′ height as per drawing	,,	1 0 0	205
17	Boxing Girders	,,	0 6 0	105
18	Constructing $1\frac{1}{8}$′ × $1\frac{1}{8}$′ burnt brick in lime mortar pillars with capital and base as per drawing complete with plastering and bond slabs	Each	10 0 0	6
19	Cement pointing to basement. 1 : 4	Sqr.	4 0 0	2.34
20	Supplying and fixing drain water pipes, carving letters for the name of the building or the parapet wall levelling the ground, etc.	L.S.	..	100

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 29th October 1935.

The attention of the public is hereby invited to the advertisement in pages 2035-2037 of the *Mysore Gazette*, dated 7th November 1935 calling for tenders for restoring Neethigere Sankannanakere, Register No. 178 of Channagiri Taluk.

Each tender must be accompanied by a Treasury challan for having deposited Rs. 100 as earnest money and to deposit a further earnest deposit of Rs. 100 after the tenders once accepted.

The last date for receiving tenders is 2 P.M., on Monday the 25th November 1935.

Abstract Notification dated 31st October 1935.

The attention of the public is hereby invited to the advertisement in pages 2037-2039 of the *Mysore Gazette*, dated 7th November 1935, calling for tenders for "Restoring Heremadala Santhiyankere Register No. 230, major tank, Channagiri Taluk".

Each tender must be accompanied by a treasury Chellan for having deposited Rs. 100 as earnest money and to deposit a further earnest deposit of Rs. 250 after the tenders are accepted.

The last date for receiving tenders is 2 P.M., on Monday the 25th November 1935.

B. KRISHNA RAO,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 7th November 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 11th December 1935, for improving the Feeder Channel to Hirekerehally Tank in Molkalmuru Taluk, Chitaldrug District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed within the time to be fixed in the agreement.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained on office days from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 450 (Four hundred and fifty) in cash, Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the Feeder Channel to Hirekerehalli Tank in Molkalmuru" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for improving the Feeder Channel to Hirekerehalli Tank in Molkalmuru Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	I. Widening the channel.				
1	Jungle clearing roots entirely grubbed up ..	Mile	50 0 0	3¾	187
2	Widening the channel and forming the bank with the excavated stuff wherever possible—				
	Ordinary soil	C.yd.	0 4 0	3,365	841
	Stoney soil	,,	0 6 0	900	338
	Soft rock	,,	0 7 0	4,639	2,030
	Hard rock	,,	2 0 0	1,399	2,798
3	Silt clearing	,,	0 2 6	3,404	532
4	Forming the bank with fresh earth with watering and tamping	,,	0 4 0	1,403	351
5	Providing bund grade stones with painting and figuring which are mixed with mud slab ..	Each	2 8 0	3	8
6	Blasting rock which are in the bed of the channel	L.S.	Rupees	..	100
	II. Relieving Weir.				
1	R. weir of 60′ long in 5–1 resetting the apron with the available stuff	C.yd.	0 12 0	20	15
2	R. weir of 52′ long in 6–2 resetting apron ..	,,	0 12 0	12	9
3	Raising the body wall by providing coping slabs with joggle joints and cement pointing ..	S.ft.	0 8 0	104	52
4	R. weir of 60′ long in 6–3 lowering weir by 1 ft. ..	C.ft.	0 0 6	90	3
5	Providing coping slabs of 3″ thick with joggle joints and cement pointing	S.ft.	0 8 0	90	45
6	Miscellaneous works such as plastering wings, etc. .	L. S.	Rupees	..	18

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	III. Head Sluice.				
1	Dismantling the head wall, etc.	C.ft.	0 0 6	773	24
2	Clearing site for waterway hard gravelly soil ..	C.yd.	0 5 0	889	278
3	Blasting stray boulders at the site ..	L. S.	Rupees	..	50
4	Earthwork excavation	C.yd.	0 5 0	3	1
5	Surki concrete with stone jelly	,,	0 5 0	68	21
6	Burnt stone in surki mortar	,,	0 6 0	219	83
7	Burnt stone slabs 6″ thick dressed and fixed ..	S.ft.	0 10 0	68	42
8	Fixing old burnt stone slabs in surki mortar over the head wall	S.ft.	0 2 0	20	3
9	Pointing with cement	Sqr.	5 0 0	2·00	10
10	Providing gearing rod and shutters for head sluice..	Each	75 0 0	2	150
11	Revetting the sides of the halla bank	C.yd.	1 8 0	56	84
	IV. Sluices.				
	Providing locking arrangements to the existing sluices which are in good condition	Each	50 0 0	5	250
	V. Cart Bridges.				
1	Earthwork excavation	C.yd.	0 4 0	6	2
2	Burnt stone in surki mortar	C.ft.	0 6 0	444	166
3	Burnt stone slabs 6″ thick dressed and fixed ..	S.ft.	0 10 0	51	32
4	Providing and fixing pillars 9″ sqr.	Each	0 14 0	23	20
5	Pointing with surki mortar	Sqr.	2 8 0	2·02	5
6	Burnt stone slabs for parapet wall of 3″ thick fairly dressed and fixed in mortar	S.ft.	0 5 0	60	19
7	Refixing old burnt stone slabs in mortar ..	S.ft.	0 2 0	120	15
8	Providing guard stones (3′×1′×6″)	No.	1 8 0	4	6
	Total ..				265
	Cost for two cart bridges 265×2—				530
	VI. Repairs to Acqueduct. ..	L. S.	Rupees	..	100
	Total ..				8,953
	Contingencies and other unforeseen items ..				447
	Grand Total ..				9,400

R. TIPPAIYA,
Executive Engineer.

MEDICAL DEPARTMENT

MINTO OPHTHALMIC HOSPITAL, BANGALORE.

Abstract Notification dated 31st October 1935.

Sealed tenders for the supply of " Bedding and Colthing " required for the Minto Ophthalmic Hospital, Bangalore, during the Official year 1935-36 will be received by the undersigned on Monday the 2nd December 1935 at 11 A.M. For full details, please see pages 2039-2040, Part VI of *Mysore Gazette*, dated 7th November 1935.

B. K. NARAYANA RAO,
Superintendent.